


| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-1 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2016.40 57.10 | 4848.40 137.30 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2016.40 57.10 | 4759.40 134.80 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2016.40 57.10 | 4706.75 133.30 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2016.40 57.10 | 4670.05 132.25 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1600.00 45.30 | 3777.75 107.00 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1600.00 45.30 | 3701.00 104.80 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1600.00 45.30 | 3655.70 103.55 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1600.00 45.30 | 3624.20 102.65 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1463.65 41.45 | 4080.10 115.55 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1463.65 41.45 | 3990.75 113.00 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1463.65 41.45 | 3939.35 111.55 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1463.65 41.45 | 3901.40 110.50 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3563.25 100.90 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 3448.70 97.65 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1183.80 33.55 | 3381.40 95.75 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1183.80 33.55 | 3332.95 94.40 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-2 | Same as item 10-1 but in 1:2:4 concrete hollow block masonry. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2016.40 57.10 | 5479.45 155.20 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2016.40 57.10 | 5368.40 152.05 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2016.40 57.10 | 5279.05 149.50 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2016.40 57.10 | 5226.40 148.00 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2016.40 57.10 | 5189.70 147.00 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1600.00 45.30 | 4263.45 120.75 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1600.00 45.30 | 4166.85 118.00 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1600.00 45.30 | 4091.35 115.85 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1600.00 45.30 | 4046.05 114.60 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1600.00 45.30 | 4014.55 113.70 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1463.65 41.45 | 4666.30 132.15 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1463.65 41.45 | 4554.00 128.95 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1463.65 41.45 | 4464.65 126.45 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1463.65 41.45 | 4412.05 124.95 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1463.65 41.45 | 4375.30 123.90 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1183.80 33.55 | 4097.25 116.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3953.60 111.95 |



| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1183.80 | 3837.85 |
| | | Cu.ft. | 33.55 | 108.70 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 3771.75 |
| | | Cu.ft. | 33.55 | 106.80 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 3723.30 |
| | | Cu.ft. | 33.55 | 105.45 |
| 10-3 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2283.30 | 5093.65 |
| | | Cu.ft. | 64.65 | 144.25 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2283.30 | 5005.50 |
| | | Cu.ft. | 64.65 | 141.75 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2283.30 | 4952.90 |
| | | Cu.ft. | 64.65 | 140.25 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2283.30 | 4916.15 |
| | | Cu.ft. | 64.65 | 139.25 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1866.90 | 4028.75 |
| | | Cu.ft. | 52.85 | 114.10 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1866.90 | 3952.00 |
| | | Cu.ft. | 52.85 | 111.90 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1866.90 | 3907.95 |
| | | Cu.ft. | 52.85 | 110.70 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1866.90 | 3875.25 |
| | | Cu.ft. | 52.85 | 109.75 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1714.15 | 4313.50 |
| | | Cu.ft. | 48.55 | 122.15 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1714.15 | 4224.15 |
| | | Cu.ft. | 48.55 | 119.65 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1714.15 | 4172.75 |
| | | Cu.ft. | 48.55 | 118.15 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1714.15 | 4136.05 |
| | | Cu.ft. | 48.55 | 117.15 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3546.15 100.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 3431.65 97.20 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1183.80 33.55 | 3364.30 95.30 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1183.80 33.55 | 3317.10 93.95 |
| 10-4 | Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry. | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2283.30 64.65 | 5721.90 162.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2283.30 64.65 | 5612.10 158.95 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2283.30 64.65 | 5522.75 156.40 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2283.30 64.65 | 5470.10 154.90 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2283.30 64.65 | 5433.40 153.90 |
| b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1866.90 52.85 | 4512.00 127.80 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1866.90 52.85 | 4416.65 125.10 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1866.90 52.85 | 4339.90 122.90 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1866.90 52.85 | 4295.85 121.65 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1866.90 52.85 | 4264.35 120.75 |
| c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1183.80 33.55 | 4359.55 123.45 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 4248.55 120.30 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 4160.40 117.80 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|--------|------------|-----------|
| | | | Labour | Composite |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 4107.75 |
| | | Cu.ft. | 33.55 | 116.35 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 4071.05 |
| | | Cu.ft. | 33.55 | 115.30 |
|  | | | | |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1183.80 | 4076.50 |
| | | Cu.ft. | 33.55 | 115.45 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1183.80 | 3934.10 |
| | | Cu.ft. | 33.55 | 111.40 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1183.80 | 3819.55 |
| | | Cu.ft. | 33.55 | 108.15 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 3752.25 |
| | | Cu.ft. | 33.55 | 106.25 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 3705.00 |
| | | Cu.ft. | 33.55 | 104.95 |
| 10-5 | Extra for hollow block masonry in first floor superstructure. | Cu.m. | 401.95 | 401.95 |
| | | Cu.ft. | 11.40 | 11.40 |
| 10-6 | Extra for hollow block masonry in every additional floor above first floor. | Cu.m. | 321.85 | 321.85 |
| | | Cu.ft. | 9.10 | 9.10 |
| 10-7 | Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 83.55 | 98.15 |
| | | Cu.ft. | 2.35 | 2.80 |