


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	4652.30 131.75
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	4568.65 129.40
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	4520.85 128.05
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4485.50 127.05
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3626.80 102.70
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3555.30 100.70
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3514.35 99.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3483.85 98.65
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	3898.70 110.40
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	3815.55 108.05
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	3767.70 106.70
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	3732.35 105.70
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3397.90 96.25
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3291.30 93.20
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3228.65 91.45
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3184.70 90.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5239.00 148.35
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5135.65 145.45
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5052.45 143.10
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5004.65 141.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4969.25 140.75
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4077.80 115.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3989.00 112.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3917.55 110.95
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3876.55 109.80
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3847.30 108.95
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	4443.30 125.85
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4339.95 122.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4256.75 120.55
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4207.75 119.15
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4173.60 118.20
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	3893.90 110.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3761.35 106.50



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3653.55
		Cu.ft.	33.55	103.45
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3592.10
		Cu.ft.	33.55	101.75
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3546.95
		Cu.ft.	33.55	100.45
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	4899.20
		Cu.ft.	64.65	138.75
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	4816.00
		Cu.ft.	64.65	136.40
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	4768.20
		Cu.ft.	64.65	135.05
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	4732.85
		Cu.ft.	64.65	134.05
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	3877.80
		Cu.ft.	52.85	109.80
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	3807.55
		Cu.ft.	52.85	107.85
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	3766.55
		Cu.ft.	52.85	106.65
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	3736.10
		Cu.ft.	52.85	105.80
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4133.35
		Cu.ft.	48.55	117.05
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4050.15
		Cu.ft.	48.55	114.70
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4001.10
		Cu.ft.	48.55	113.30
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	3966.95
		Cu.ft.	48.55	112.35

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3380.85 95.75
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3275.45 92.75
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3212.75 91.00
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3168.85 89.75
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	5483.90 155.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	5380.55 152.40
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	5297.35 150.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	5249.55 148.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	5214.20 147.65
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4327.60 122.55
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4238.80 120.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4168.55 118.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4126.35 116.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4097.10 116.05
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4139.05 117.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4035.70 114.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3952.50 111.95

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3904.70
		Cu.ft.	33.55	110.60
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3869.30
		Cu.ft.	33.55	109.60
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	3874.40
		Cu.ft.	33.55	109.75
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	3741.85
		Cu.ft.	33.55	105.95
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3636.45
		Cu.ft.	33.55	103.00
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3573.80
		Cu.ft.	33.55	101.20
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3529.85
		Cu.ft.	33.55	99.95
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80