


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	4848.40 137.30
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	4759.40 134.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	4706.75 133.30
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	4670.05 132.25
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	3777.75 107.00
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	3701.00 104.80
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	3655.70 103.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	3624.20 102.65
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4080.10 115.55
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	3990.75 113.00
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	3939.35 111.55
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	3901.40 110.50
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3563.25 100.90
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3448.70 97.65
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3381.40 95.75
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3332.95 94.40

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2016.40 57.10	5479.45 155.20
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2016.40 57.10	5368.40 152.05
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2016.40 57.10	5279.05 149.50
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2016.40 57.10	5226.40 148.00
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2016.40 57.10	5189.70 147.00
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1600.00 45.30	4263.45 120.75
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1600.00 45.30	4166.85 118.00
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1600.00 45.30	4091.35 115.85
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1600.00 45.30	4046.05 114.60
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1600.00 45.30	4014.55 113.70
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1463.65 41.45	4666.30 132.15
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1463.65 41.45	4554.00 128.95
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1463.65 41.45	4464.65 126.45
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1463.65 41.45	4412.05 124.95
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1463.65 41.45	4375.30 123.90
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4097.25 116.05
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3953.60 111.95

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3837.85
		Cu.ft.	33.55	108.70
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3771.75
		Cu.ft.	33.55	106.80
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3723.30
		Cu.ft.	33.55	105.45
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2283.30	5093.65
		Cu.ft.	64.65	144.25
ii)	Cement sand mortar 1 : 4	Cu.m.	2283.30	5005.50
		Cu.ft.	64.65	141.75
iii)	Cement sand mortar 1 : 5	Cu.m.	2283.30	4952.90
		Cu.ft.	64.65	140.25
iv)	Cement sand mortar 1 : 6	Cu.m.	2283.30	4916.15
		Cu.ft.	64.65	139.25
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1866.90	4028.75
		Cu.ft.	52.85	114.10
ii)	Cement sand mortar 1 : 4	Cu.m.	1866.90	3952.00
		Cu.ft.	52.85	111.90
iii)	Cement sand mortar 1 : 5	Cu.m.	1866.90	3907.95
		Cu.ft.	52.85	110.70
iv)	Cement sand mortar 1 : 6	Cu.m.	1866.90	3875.25
		Cu.ft.	52.85	109.75
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1714.15	4313.50
		Cu.ft.	48.55	122.15
ii)	Cement sand mortar 1 : 4	Cu.m.	1714.15	4224.15
		Cu.ft.	48.55	119.65
iii)	Cement sand mortar 1 : 5	Cu.m.	1714.15	4172.75
		Cu.ft.	48.55	118.15
iv)	Cement sand mortar 1 : 6	Cu.m.	1714.15	4136.05
		Cu.ft.	48.55	117.15

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	3546.15 100.45
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	3431.65 97.20
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1183.80 33.55	3364.30 95.30
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1183.80 33.55	3317.10 93.95
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2283.30 64.65	5721.90 162.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2283.30 64.65	5612.10 158.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2283.30 64.65	5522.75 156.40
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2283.30 64.65	5470.10 154.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2283.30 64.65	5433.40 153.90
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1866.90 52.85	4512.00 127.80
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1866.90 52.85	4416.65 125.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1866.90 52.85	4339.90 122.90
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1866.90 52.85	4295.85 121.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1866.90 52.85	4264.35 120.75
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1183.80 33.55	4359.55 123.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1183.80 33.55	4248.55 120.30
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1183.80 33.55	4160.40 117.80

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	4107.75
		Cu.ft.	33.55	116.35
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	4071.05
		Cu.ft.	33.55	115.30
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1183.80	4076.50
		Cu.ft.	33.55	115.45
ii)	Cement sand mortar 1 : 3	Cu.m.	1183.80	3934.10
		Cu.ft.	33.55	111.40
iii)	Cement sand mortar 1 : 4	Cu.m.	1183.80	3819.55
		Cu.ft.	33.55	108.15
iv)	Cement sand mortar 1 : 5	Cu.m.	1183.80	3752.25
		Cu.ft.	33.55	106.25
v)	Cement sand mortar 1 : 6	Cu.m.	1183.80	3705.00
		Cu.ft.	33.55	104.95
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	401.95	401.95
		Cu.ft.	11.40	11.40
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	321.85	321.85
		Cu.ft.	9.10	9.10
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80