

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
20-9	Fixing A.P.M. and/or O.F. outlet blocks including dressing of bricks.			
	a) For channel depth upto 1.5 ft. (0.5 m.)	Each	538.00	621.45
	b) For channel depth above 1.5 ft. to 3 ft. (0.5 m. to 1m)	Each	627.70	739.50
	c) For channel depth above 3 ft. to 5 ft. (1 m. to 1.5 m)	Each	807.05	947.20
	d) For channel depth above 5 ft. (1.5 m)	Each	1076.05	1216.20
20-10	Repairing damaged reducing collar of Hume pipe outlets.	Each	448.35	644.70
20-11	Laying iron pipes for outlets	R.M. R.ft.	71.75 21.85	71.75 21.85
20-12	Water allowance for constructing outlets or culverts when canal water is not flowing			
	a) For channel depth upto 1.5 ft. (0.5 m.)	Each	507.50	507.50
	b) For channel depth above 1.5 ft. to 3 ft. (0.5 m. to 1m)	Each	634.40	634.40
	c) For channel depth above 3 ft. to 5 ft. (1 m. to 1.5 m)	Each	919.90	919.90
	d) For channel depth above 5 ft. (1.5 m)	Each	1268.80	1268.80
20-13	Hoisting and placing R.C. slab or stone in position on outlets or W.C culverts.	Each	427.60	427.60
20-14	Fixing pipe culverts including back-filling of earth and puddling			
	a) Portion under bank	R.M. R.ft.	274.75 83.75	313.65 95.60
	b) Portion under road beyond bank	R.M. R.ft.	129.40 39.45	168.25 51.30
20-15	Removing pipe outlets and refilling earth including ramming and puddling.			
	a) Portion under bank	R.M. R.ft.	228.40 69.60	228.40 69.60
	b) Portion under road beyond bank	R.M. R.ft.	88.80 27.05	88.80 27.05
20-16	Changing pipe outlets by removing one pipe and replacing it at the same site with another pipe including earthwork and puddling			
	a) Portion under bank	R.M. R.ft.	319.70 97.45	358.60 109.30
	b) Portion under road beyond bank	R.M. R.ft.	150.05 45.75	188.95 57.60