


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6071.30 171.95
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5972.05 169.15
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5915.25 167.50
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5873.50 166.35
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4728.05 133.90
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4643.40 131.50
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4594.70 130.10
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4558.70 129.10
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5174.85 146.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5075.05 143.75
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5018.30 142.10
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4976.50 140.95
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4509.60 127.70
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4382.00 124.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4307.75 122.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4255.60 120.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6841.30 193.75
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6761.00 191.50
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6662.40 188.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6604.40 187.05
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6563.85 185.90
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5313.90 150.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5246.10 148.55
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	5161.45 146.20
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	5111.55 144.75
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	5075.55 143.75
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5882.40 166.60
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5802.10 164.30
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5703.55 161.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5645.55 159.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5604.95 158.75
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5129.35 145.25
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5026.45 142.35

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4898.85
		Cu.ft.	36.95	138.75
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4824.60
		Cu.ft.	36.95	136.65
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4772.45
		Cu.ft.	36.95	135.15
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6362.20
		Cu.ft.	71.55	180.20
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6263.65
		Cu.ft.	71.55	177.40
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6205.65
		Cu.ft.	71.55	175.75
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6165.05
		Cu.ft.	71.55	174.60
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	5025.75
		Cu.ft.	59.05	142.35
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4941.05
		Cu.ft.	59.05	139.95
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4892.40
		Cu.ft.	59.05	138.55
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4856.40
		Cu.ft.	59.05	137.55
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5444.10
		Cu.ft.	53.90	154.20
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5345.55
		Cu.ft.	53.90	151.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5288.75
		Cu.ft.	53.90	149.80
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5248.20
		Cu.ft.	53.90	148.65

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4486.45 127.05
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4360.05 123.50
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4287.00 121.40
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4233.65 119.90
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	7128.00 201.85
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	7047.70 199.60
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6949.10 196.80
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6892.30 195.20
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6851.75 194.05
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5609.15 158.85
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5540.15 156.90
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5455.45 154.50
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5406.80 153.10
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5372.05 152.15
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5544.30 157.00
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5464.00 154.75
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5366.65 152.00



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5308.65
		Cu.ft.	36.95	150.35
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5268.10
		Cu.ft.	36.95	149.20
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	5103.75
		Cu.ft.	36.95	144.55
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	5002.05
		Cu.ft.	36.95	141.65
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4875.65
		Cu.ft.	36.95	138.10
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4801.45
		Cu.ft.	36.95	136.00
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4749.25
		Cu.ft.	36.95	134.50
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80