

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5948.70 168.45
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5852.10 165.75
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5795.30 164.15
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5755.55 163.00
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4634.05 131.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4551.15 128.90
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4503.50 127.55
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4468.20 126.55
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5060.60 143.30
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4964.05 140.60
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4907.25 139.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4867.55 137.85
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4405.60 124.75
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4281.85 121.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4209.15 119.20
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4156.85 117.70




Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	6706.15 189.90
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	6625.35 187.65
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	6528.80 184.90
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	6472.00 183.30
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	6432.30 182.15
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5211.05 147.60
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5141.60 145.60
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	5058.70 143.25
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	5011.00 141.90
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4975.75 140.90
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5758.55 163.10
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	5677.75 160.80
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	5581.25 158.05
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	5524.40 156.45
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	5483.50 155.30
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5017.90 142.10
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4914.35 139.20

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4789.40
		Cu.ft.	36.95	135.65
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4716.70
		Cu.ft.	36.95	133.60
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4665.60
		Cu.ft.	36.95	132.15
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	6240.20
		Cu.ft.	71.55	176.75
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	6143.65
		Cu.ft.	71.55	174.00
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	6086.85
		Cu.ft.	71.55	172.40
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	6047.15
		Cu.ft.	71.55	171.25
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4931.75
		Cu.ft.	59.05	139.65
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4848.80
		Cu.ft.	59.05	137.30
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4801.15
		Cu.ft.	59.05	135.95
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4767.10
		Cu.ft.	59.05	135.00
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	5331.05
		Cu.ft.	53.90	151.00
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	5234.50
		Cu.ft.	53.90	148.25
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	5178.95
		Cu.ft.	53.90	146.65
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	5139.20
		Cu.ft.	53.90	145.55

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4384.85 124.20
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4261.10 120.70
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	4188.40 118.60
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	4137.35 117.15
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
<b>a) 4" (100 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6994.05 198.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6913.25 195.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6816.75 193.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	6761.15 191.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	6721.45 190.35
<b>b) 6" (150 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	5506.25 155.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	5436.85 153.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	5353.90 151.65
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	5306.25 150.30
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	5272.25 149.30
<b>c) 8" (200 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	5420.45 153.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	5339.65 151.20
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	5244.35 148.50



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	5187.55
		Cu.ft.	36.95	146.90
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	5147.80
		Cu.ft.	36.95	145.80
				
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4993.50
		Cu.ft.	36.95	141.40
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4889.95
		Cu.ft.	36.95	138.50
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4766.20
		Cu.ft.	36.95	135.00
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4693.50
		Cu.ft.	36.95	132.90
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4642.45
		Cu.ft.	36.95	131.50
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80