


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.80 62.60	5792.95 164.05
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.80 62.60	5684.90 161.00
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.80 62.60	5621.55 159.20
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.80 62.60	5577.10 157.95
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4924.85 139.45
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4815.80 136.40
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4753.65 134.65
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4708.00 133.35
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1612.20 45.65	4523.05 128.10
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1612.20 45.65	4430.45 125.45
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1612.20 45.65	4375.95 123.95
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1612.20 45.65	4337.90 122.85
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1303.40 36.90	4315.25 122.20
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1303.40 36.90	4177.00 118.30
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1303.40 36.90	4095.85 116.00
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1303.40 36.90	4037.55 114.35

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.80 62.60	6394.70 181.10
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.80 62.60	6288.60 178.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.80 62.60	6180.80 175.05
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.80 62.60	6117.40 173.25
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.80 62.60	6073.00 172.00
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	5481.95 155.25
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	5375.85 152.25
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	5268.05 149.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	5204.70 147.40
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	5160.25 146.15
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1612.20 45.65	4985.45 141.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1612.20 45.65	4894.35 138.60
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1612.20 45.65	4801.75 136.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1612.20 45.65	4748.50 134.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1612.20 45.65	4709.20 133.35
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1303.40 36.90	4823.80 136.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1303.40 36.90	4687.75 132.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1303.40	4548.30
		Cu.ft.	36.90	128.80
iv)	Cement sand mortar 1 : 5	Cu.m.	1303.40	4467.15
		Cu.ft.	36.90	126.50
v)	Cement sand mortar 1 : 6	Cu.m.	1303.40	4408.80
		Cu.ft.	36.90	124.85
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	936.41	4809.25
		Cu.ft.	26.50	136.20
ii)	Cement sand mortar 1 : 4	Cu.m.	936.41	4701.45
		Cu.ft.	26.50	133.15
iii)	Cement sand mortar 1 : 5	Cu.m.	936.41	4639.25
		Cu.ft.	26.50	131.40
iv)	Cement sand mortar 1 : 6	Cu.m.	936.41	4593.65
		Cu.ft.	26.50	130.10
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	772.30	4233.15
		Cu.ft.	21.85	119.90
ii)	Cement sand mortar 1 : 4	Cu.m.	772.30	4125.35
		Cu.ft.	21.85	116.85
iii)	Cement sand mortar 1 : 5	Cu.m.	772.30	4063.15
		Cu.ft.	21.85	115.05
iv)	Cement sand mortar 1 : 6	Cu.m.	772.30	4018.75
		Cu.ft.	21.85	113.80
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	705.33	3768.65
		Cu.ft.	20.00	106.75
ii)	Cement sand mortar 1 : 4	Cu.m.	705.33	3676.05
		Cu.ft.	20.00	104.10
iii)	Cement sand mortar 1 : 5	Cu.m.	705.33	3621.55
		Cu.ft.	20.00	102.55
iv)	Cement sand mortar 1 : 6	Cu.m.	705.33	3583.50
		Cu.ft.	20.00	101.50

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	483.48 13.70	3637.70 103.00
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	483.48 13.70	3498.20 99.05
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	483.48 13.70	3418.30 96.80
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	483.48 13.70	3359.95 95.15
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	936.41 26.50	5408.75 153.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	936.41 26.50	5302.65 150.15
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	936.41 26.50	5194.90 147.10
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	936.41 26.50	5132.70 145.35
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	936.41 26.50	5087.10 144.05
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	772.30 21.85	4228.60 119.75
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	772.30 21.85	4138.70 117.20
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	772.30 21.85	4046.15 114.60
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	772.30 21.85	3991.60 113.05
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	772.30 21.85	3953.55 111.95
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	555.49 15.75	4485.85 127.05
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	555.49 15.75	4380.95 124.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	555.49 15.75	4273.15 121.00



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	555.49	4209.80
		Cu.ft.	15.75	119.20
v)	Cement sand mortar 1 : 6	Cu.m.	555.49	4165.35
		Cu.ft.	15.75	117.95
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	483.48	4143.80
		Cu.ft.	13.70	117.35
ii)	Cement sand mortar 1 : 3	Cu.m.	483.48	4007.75
		Cu.ft.	13.70	113.50
iii)	Cement sand mortar 1 : 4	Cu.m.	483.48	3868.30
		Cu.ft.	13.70	109.55
iv)	Cement sand mortar 1 : 5	Cu.m.	483.48	3788.35
		Cu.ft.	13.70	107.30
v)	Cement sand mortar 1 : 6	Cu.m.	483.48	3730.05
		Cu.ft.	13.70	105.65
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80