| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. |
|------------|---|------------------------|------------------|------------------|-------------------------|
| | | | Labour | Composite | Tech. Specs. |
| 2-1 | Loading or unloading into or from mobile trucks, coarse aggregate, sand, stone/ brick ballast, surkhi, ashes, kankar, brick/stone bats, coal or lime etc. lead upto 100 ft (30 m) | | 127.10 3.60 | 158.88 4.50 | 2.1.1 2.1.3 |
| 2-2 | Loading or unloading bricks or tiles into or from mobile trucks properly laid and stacked lead upto 100 ft (30 m) | 1000 Nos. | 900.00 | 1,116.00 | 2.1.1 2.1.3 |
| 2-3 | Loading or unloading into or from mobile trucks cement in bags (inside or outside the godown) and stacking lead upto | 100 Nos. | 900.00 | 1,125.00 | 2.1.1 2.1.3 |
| 2-4 | Loading or unloading into or from mobile trucks empty cement bags (inside or outside the godown) and stacking lead upto 100 ft (30 m) | | 10.80 | 13.39 | 2.1.1 2.1.3 |
| 2-5 | Loading or unloading into or from mobile trucks (inside or outside the godown) and stacking, white lime in bags lead upto 100 ft (30 m) | | 16.90 8.60 | 20.96 10.65 | 2.1.1 2.1.3 |
| 2-6 | Loading or unloading into or from mobile trucks structural steel, R.S joists etc. lead upto 100 ft (30 m) | Ton | 43.90 | 54.85 | 2.1.1 2.1.3 |
| 2-7 | Loading or unloading 205 litre drums fuel into or from mobile trucks, lead upto 100 ft (30 m) | Each | 43.90 | 54.44 | 2.1.1 2.1.3 |
| 2-8 | Loading or unloading packages of sorts weighing upto 50 | Each | 43.90 | 54.44 | 2.1.1 2.1.3 |
| 2-9 | Loading or unloading timber logs or timber for shuttering, into or from mobile trucks including stacking lead upto 100 ft (30 | Ton | 153.20 | 190.00 | 2.1.3 2.1.1 2.1.3 |
| 2-10 | Loading or unloading bhoosa into or from mobile trucks lead upto 150 ft. (45 m) | % Kg. Cwt. | 43.90 22.30 | 54.44 27.65 | 2.1.1 2.1.3 |
| 2-11 | Loading or unloading timber scrap or wooden plugs into or from mobile trucks including stacking and lead upto 100 ft | Ton | 272.10 | 337.40 | 2.1.1 2.1.3 |
| 2-12 | Loading or unloading pitching stone or spawl from mobile trucks including clearing | Cu.m. Cu.ft | 402.80 11.40 | 499.47 14.15 | 2.1.1 2.1.3 |
| 2-13 | Loading or unloading building stone including clearing | Cu.m. Cu.ft | 540.00 15.30 | 669.60 18.95 | 2.1.1 2.1.3 |
| 2-14 a) | Unloading oils. Crude oil (to be pumped from tanker into tank) | 1000 Litre % Gallon | 149.60 68.00 | 185.50 84.35 | 2.1.1 2.1.3 |
| b) | Crude oil (drained by gravity) | 1000 Litre % Gallon | 149.60 68.00 | 185.50 84.35 | |
| c) | Fuel oil into empty drums including stacking upto 100 ft (30 i | Ton | 251 45 | 244.05 | |
| d) | Petrol (4.5 litre tin) | Ton 100 Nos. | 251.45 337.50 | 311.85 418.50 | |
| e) | Kerosine (18 litre tin) | 100 Nos. | 676.15 | 838.43 | |
| | | | | | |

| Sr. No. | Description | Unit | Rate (Rs.) | | Ref. |
|---------|--|----------------|-------------------|-------------------|-----------------|
| | | | Labour | Composite | Tech. Specs. |
| 2-15 | Removing and stacking lead upto 100 ft (30 m) | | | | 2.1.1 2.1.3 |
| a) | Stone, spawl, brick bats, shingle, sand, lime, surkhi, ashes, kankar and coal etc. | Cu.m. Cu.ft | 127.10 3.60 | 157.60 4.45 | 2.110 |
| b) | Bricks | % Nos. | 900.00 | 1,116.00 | |
| c) | Rails, girders, pipes, cement etc. | Ton | 365.80 | 453.55 | |
| d) | Bailey bridges & wooden structural members | % Nos. | 1,434.40 40.60 | 1,793.00 50.80 | |
| 2-16 | Loading into mobile trucks girders, rails, permanent way material, iron work. pipes etc including lead upto 100 ft (30 m) and stacking | Ton | 348.60 | 435.75 | 2.1.1 2.1.3 |
| 2-17 | Unloading from mobile trucks girders, permanent way material, iron work, pipes, etc. lead upto 100 ft (30 m) but excluding stacking. | Ton | 173.75 | 217.20 | 2.1.1 2.1.3 |
| 2-18 | Loading or unloading bitumen, asphalt or tar in drums, into or from mobile trucks lead upto 100 ft (30 m) | Ton | 257.15 | 257.15 | 2.1.1 2.1.3 |
| 2-19 | Loading bailey bridge wooden structural members including stacking lead upto 100 ft (30m) | Cu.m. Cu.ft | 180.00 5.10 | 225.00 6.35 | 2.1.1 2.1.3 |
| 2-20 | Unloading bailey bridge wooden structural members excluding stacking lead upto 100 ft (30m) | % Nos. | 95.60 2.70 | 119.50 3.40 | 2.1.1 2.1.3 |
| 2-21 | Loading into mobile trucks, steel fabrication/bars including lead upto 100 ft (30m) and stacking inside trucks. | Ton | 628.75 | 628.75 | 2.1.1 2.1.3 |
| 2-22 | Unloading from mobile trucks, steel fabrication/bars including lead upto 100 ft (30m) and stacking | Ton | 342.90 | 342.90 | 2.1.1 2.1.3 |