

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	3585.70 101.55
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	3524.20 99.80
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	3487.10 98.75
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	3461.50 98.05
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	2674.20 75.75
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	2621.50 74.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	2589.55 73.35
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	2567.60 72.70
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	2958.45 83.80
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	2895.75 82.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	2859.85 81.00
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	2833.00 80.25
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2551.85 72.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2471.55 70.00
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2424.25 68.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2391.30 67.70

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1616.25 45.75	4072.30 115.35
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1616.25 45.75	3948.15 111.80
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1616.25 45.75	3885.40 110.05
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1616.25 45.75	3849.55 109.00
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1616.25 45.75	3822.70 108.25
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1164.60 33.00	3052.95 86.45
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1164.60 33.00	2946.35 83.45
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1164.60 33.00	2892.40 81.90
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1164.60 33.00	2861.65 81.05
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1164.60 33.00	2838.50 80.40
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1141.35 32.30	3412.05 96.65
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1141.35 32.30	3287.85 93.10
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1141.35 32.30	3225.15 91.35
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1141.35 32.30	3189.25 90.30
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1141.35 32.30	3162.40 89.55
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	2983.30 84.50
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2822.75 79.95

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	2742.45
		Cu.ft.	25.85	77.65
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	2696.35
		Cu.ft.	25.85	76.35
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	2662.20
		Cu.ft.	25.85	75.40
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1797.35	3750.95
		Cu.ft.	50.90	106.25
ii)	Cement sand mortar 1 : 4	Cu.m.	1797.35	3689.45
		Cu.ft.	50.90	104.50
iii)	Cement sand mortar 1 : 5	Cu.m.	1797.35	3653.60
		Cu.ft.	50.90	103.45
iv)	Cement sand mortar 1 : 6	Cu.m.	1797.35	3626.75
		Cu.ft.	50.90	102.70
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1345.70	2844.35
		Cu.ft.	38.10	80.55
ii)	Cement sand mortar 1 : 4	Cu.m.	1345.70	2791.60
		Cu.ft.	38.10	79.05
iii)	Cement sand mortar 1 : 5	Cu.m.	1345.70	2759.65
		Cu.ft.	38.10	78.15
iv)	Cement sand mortar 1 : 6	Cu.m.	1345.70	2737.70
		Cu.ft.	38.10	77.55
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1311.00	3114.70
		Cu.ft.	37.15	88.20
ii)	Cement sand mortar 1 : 4	Cu.m.	1311.00	3053.20
		Cu.ft.	37.15	86.45
iii)	Cement sand mortar 1 : 5	Cu.m.	1311.00	3016.10
		Cu.ft.	37.15	85.40
iv)	Cement sand mortar 1 : 6	Cu.m.	1311.00	2990.50
		Cu.ft.	37.15	84.70

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	2539.65 71.90
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2459.35 69.65
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	912.20 25.85	2413.25 68.35
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	912.20 25.85	2379.10 67.40
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
a) 4" (100 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1797.35 50.90	4235.10 119.95
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1797.35 50.90	4110.90 116.40
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1797.35 50.90	4049.45 114.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1797.35 50.90	4013.55 113.65
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1797.35 50.90	3986.70 112.90
b) 6" (150 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1345.70 38.10	3220.65 91.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1345.70 38.10	3114.00 88.20
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1345.70 38.10	3061.30 86.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1345.70 38.10	3030.55 85.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1345.70 38.10	3007.40 85.15
c) 8" (200 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	912.20 25.85	3164.60 89.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	912.20 25.85	3040.40 86.10
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	912.20 25.85	2977.70 84.35

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	2941.85
		Cu.ft.	25.85	83.30
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	2916.20
		Cu.ft.	25.85	82.60
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	912.20	2968.65
		Cu.ft.	25.85	84.05
ii)	Cement sand mortar 1 : 3	Cu.m.	912.20	2809.35
		Cu.ft.	25.85	79.55
iii)	Cement sand mortar 1 : 4	Cu.m.	912.20	2729.05
		Cu.ft.	25.85	77.30
iv)	Cement sand mortar 1 : 5	Cu.m.	912.20	2682.95
		Cu.ft.	25.85	76.00
v)	Cement sand mortar 1 : 6	Cu.m.	912.20	2650.00
		Cu.ft.	25.85	75.05
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	273.85	273.85
		Cu.ft.	7.75	7.75
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	217.75	217.75
		Cu.ft.	6.15	6.15
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80