


| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-1 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2016.40 57.10 | 4818.30 136.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2016.40 57.10 | 4733.65 134.05 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2016.40 57.10 | 4685.20 132.70 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2016.40 57.10 | 4649.40 131.65 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1600.00 45.30 | 3753.60 106.30 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1600.00 45.30 | 3682.45 104.30 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1600.00 45.30 | 3639.75 103.10 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1600.00 45.30 | 3610.10 102.25 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1463.65 41.45 | 4052.55 114.75 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1463.65 41.45 | 3968.30 112.40 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1463.65 41.45 | 3918.70 111.00 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1463.65 41.45 | 3884.10 110.00 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3537.65 100.20 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 3429.70 97.15 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1183.80 33.55 | 3366.20 95.35 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1183.80 33.55 | 3320.50 94.05 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-2 | Same as item 10-1 but in 1:2:4 concrete hollow block masonry. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2016.40 57.10 | 5388.05 152.60 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2016.40 57.10 | 5301.45 150.15 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2016.40 57.10 | 5217.20 147.75 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2016.40 57.10 | 5168.80 146.40 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2016.40 57.10 | 5133.00 145.35 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1600.00 45.30 | 4191.30 118.70 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1600.00 45.30 | 4116.90 116.60 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1600.00 45.30 | 4044.50 114.55 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1600.00 45.30 | 4001.80 113.35 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1600.00 45.30 | 3972.15 112.50 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1463.65 41.45 | 4579.00 129.70 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1463.65 41.45 | 4492.40 127.25 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1463.65 41.45 | 4408.15 124.85 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1463.65 41.45 | 4359.75 123.45 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1463.65 41.45 | 4323.90 122.45 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1183.80 33.55 | 4011.95 113.60 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3899.70 110.45 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1183.80 | 3791.75 |
| | | Cu.ft. | 33.55 | 107.40 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 3728.30 |
| | | Cu.ft. | 33.55 | 105.60 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 3683.80 |
| | | Cu.ft. | 33.55 | 104.35 |
| 10-3 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2283.30 | 5064.00 |
| | | Cu.ft. | 64.65 | 143.40 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2283.30 | 4979.75 |
| | | Cu.ft. | 64.65 | 141.05 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2283.30 | 4931.35 |
| | | Cu.ft. | 64.65 | 139.65 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2283.30 | 4896.75 |
| | | Cu.ft. | 64.65 | 138.70 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1866.90 | 4005.85 |
| | | Cu.ft. | 52.85 | 113.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1866.90 | 3933.45 |
| | | Cu.ft. | 52.85 | 111.40 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1866.90 | 3891.95 |
| | | Cu.ft. | 52.85 | 110.20 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1866.90 | 3861.10 |
| | | Cu.ft. | 52.85 | 109.35 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1714.15 | 4285.95 |
| | | Cu.ft. | 48.55 | 121.40 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1714.15 | 4201.70 |
| | | Cu.ft. | 48.55 | 119.00 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1714.15 | 4153.30 |
| | | Cu.ft. | 48.55 | 117.60 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1714.15 | 4117.50 |
| | | Cu.ft. | 48.55 | 116.60 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 3520.55 99.70 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 3412.60 96.65 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1183.80 33.55 | 3349.15 94.85 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1183.80 33.55 | 3304.65 93.60 |
| 10-4 | Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry. | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2283.30 64.65 | 5631.75 159.50 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2283.30 64.65 | 5545.15 157.05 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2283.30 64.65 | 5460.90 154.65 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2283.30 64.65 | 5412.50 153.30 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2283.30 64.65 | 5377.90 152.30 |
| b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1866.90 52.85 | 4439.90 125.75 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1866.90 52.85 | 4365.45 123.65 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1866.90 52.85 | 4294.30 121.60 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1866.90 52.85 | 4252.80 120.45 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1866.90 52.85 | 4221.95 119.55 |
| c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1183.80 33.55 | 4274.70 121.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1183.80 33.55 | 4188.10 118.60 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1183.80 33.55 | 4103.90 116.20 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|--------|------------|-----------|
| | | | Labour | Composite |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 4055.45 |
| | | Cu.ft. | 33.55 | 114.85 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 4020.85 |
| | | Cu.ft. | 33.55 | 113.85 |
|  | | | | |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1183.80 | 3991.20 |
| | | Cu.ft. | 33.55 | 113.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1183.80 | 3880.20 |
| | | Cu.ft. | 33.55 | 109.90 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1183.80 | 3773.45 |
| | | Cu.ft. | 33.55 | 106.85 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1183.80 | 3710.00 |
| | | Cu.ft. | 33.55 | 105.05 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1183.80 | 3665.50 |
| | | Cu.ft. | 33.55 | 103.80 |
| 10-5 | Extra for hollow block masonry in first floor superstructure. | Cu.m. | 401.95 | 401.95 |
| | | Cu.ft. | 11.40 | 11.40 |
| 10-6 | Extra for hollow block masonry in every additional floor above first floor. | Cu.m. | 321.85 | 321.85 |
| | | Cu.ft. | 9.10 | 9.10 |
| 10-7 | Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 83.55 | 98.15 |
| | | Cu.ft. | 2.35 | 2.80 |