


Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5291.35 149.85
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5198.80 147.25
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5144.35 145.70
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5106.35 144.60
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4138.35 117.20
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4058.95 114.95
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4013.35 113.65
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	3979.55 112.70
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	4460.00 126.30
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4367.60 123.70
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4313.15 122.15
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4275.15 121.05
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	3899.25 110.45
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	3780.80 107.05
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	3711.15 105.10
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	3661.10 103.70

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	5903.20 167.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5823.50 164.90
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5729.85 162.25
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5676.65 160.75
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5637.40 159.65
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	4605.75 130.45
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4537.25 128.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4457.85 126.25
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4411.00 124.90
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4378.45 124.00
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	5024.00 142.30
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	4944.30 140.05
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4851.90 137.40
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4797.45 135.85
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4759.45 134.80
	d) 12" (300 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4400.30 124.60
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4298.15 121.75

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4179.70
		Cu.ft.	36.95	118.35
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4110.05
		Cu.ft.	36.95	116.40
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4060.00
		Cu.ft.	36.95	115.00
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	a) 4" (100 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	5585.25
		Cu.ft.	71.55	158.20
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	5494.00
		Cu.ft.	71.55	155.60
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	5439.60
		Cu.ft.	71.55	154.05
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	5401.60
		Cu.ft.	71.55	153.00
	b) 6" (150 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4438.45
		Cu.ft.	59.05	125.70
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4359.05
		Cu.ft.	59.05	123.45
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4313.45
		Cu.ft.	59.05	122.15
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4280.90
		Cu.ft.	59.05	121.25
	c) 8" (200 mm) thick hollow block masonry			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	4732.90
		Cu.ft.	53.90	134.05
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	4641.70
		Cu.ft.	53.90	131.45
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	4587.30
		Cu.ft.	53.90	129.90
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	4549.30
		Cu.ft.	53.90	128.85

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
	d) 12" (300 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	3879.75 109.90
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	3762.50 106.55
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	3692.85 104.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	3644.00 103.20
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
	a) 4" (100 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6193.55 175.40
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6115.05 173.20
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	6022.65 170.55
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	5968.20 169.00
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	5930.20 167.95
	b) 6" (150 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	4903.40 138.85
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	4834.90 136.95
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	4756.75 134.70
	iv) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	4709.90 133.40
	v) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	4677.35 132.45
	c) 8" (200 mm) thick hollow block masonry			
	i) Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4689.55 132.80
	ii) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4609.85 130.55
	iii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4518.65 127.95



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4464.25
		Cu.ft.	36.95	126.45
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4426.20
		Cu.ft.	36.95	125.35
				
d) 12" (300 mm) thick hollow block masonry				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4379.55
		Cu.ft.	36.95	124.05
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4277.45
		Cu.ft.	36.95	121.15
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4158.95
		Cu.ft.	36.95	117.80
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4089.30
		Cu.ft.	36.95	115.80
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4040.45
		Cu.ft.	36.95	114.45
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80