

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-1	Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5250.75 148.70
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5158.60 146.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5106.00 144.60
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5067.20 143.50
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4107.45 116.35
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4028.95 114.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	3982.60 112.80
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	3950.40 111.90
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	4422.85 125.25
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4330.25 122.65
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4277.60 121.15
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4238.85 120.05
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
	i) Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	3864.75 109.45
	ii) Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	3746.35 106.10
	iii) Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	3678.75 104.20
	iv) Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	3629.20 102.80




Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
10-2	Same as item 10-1 but in 1:2:4 concrete hollow block masonry.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2209.50 62.55	5860.75 166.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2209.50 62.55	5776.60 163.60
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2209.50 62.55	5685.20 161.00
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2209.50 62.55	5631.40 159.50
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2209.50 62.55	5593.80 158.40
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1767.75 50.05	4573.15 129.50
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1767.75 50.05	4502.10 127.50
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1767.75 50.05	4423.55 125.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1767.75 50.05	4377.25 123.95
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1767.75 50.05	4345.05 123.05
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1611.30 45.65	4984.90 141.20
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1611.30 45.65	4900.75 138.80
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1611.30 45.65	4809.35 136.20
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1611.30 45.65	4756.75 134.70
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1611.30 45.65	4717.95 133.60
	<b>d) 12" (300 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4367.25 123.70
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4259.40 120.65



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4141.00
		Cu.ft.	36.95	117.30
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4072.15
		Cu.ft.	36.95	115.35
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4023.85
		Cu.ft.	36.95	113.95
10-3	Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure.			
	<b>a) 4" (100 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2526.70	5545.25
		Cu.ft.	71.55	157.05
ii)	Cement sand mortar 1 : 4	Cu.m.	2526.70	5453.85
		Cu.ft.	71.55	154.45
iii)	Cement sand mortar 1 : 5	Cu.m.	2526.70	5401.25
		Cu.ft.	71.55	152.95
iv)	Cement sand mortar 1 : 6	Cu.m.	2526.70	5363.65
		Cu.ft.	71.55	151.90
	<b>b) 6" (150 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	2084.95	4407.55
		Cu.ft.	59.05	124.80
ii)	Cement sand mortar 1 : 4	Cu.m.	2084.95	4329.05
		Cu.ft.	59.05	122.60
iii)	Cement sand mortar 1 : 5	Cu.m.	2084.95	4283.95
		Cu.ft.	59.05	121.30
iv)	Cement sand mortar 1 : 6	Cu.m.	2084.95	4251.75
		Cu.ft.	59.05	120.40
	<b>c) 8" (200 mm) thick hollow block masonry</b>			
i)	Cement sand mortar 1 : 3	Cu.m.	1903.75	4695.75
		Cu.ft.	53.90	133.00
ii)	Cement sand mortar 1 : 4	Cu.m.	1903.75	4604.35
		Cu.ft.	53.90	130.40
iii)	Cement sand mortar 1 : 5	Cu.m.	1903.75	4551.75
		Cu.ft.	53.90	128.90
iv)	Cement sand mortar 1 : 6	Cu.m.	1903.75	4514.15
		Cu.ft.	53.90	127.85

Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	3845.25 108.90
ii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	3728.05 105.60
iii)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	1304.90 36.95	3660.45 103.65
iv)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	1304.90 36.95	3610.90 102.25
10-4	Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry.			
<b>a) 4" (100 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2526.70 71.55	6152.35 174.25
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2526.70 71.55	6068.20 171.85
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2526.70 71.55	5978.00 169.30
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2526.70 71.55	5924.20 167.80
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2526.70 71.55	5886.60 166.70
<b>b) 6" (150 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	2084.95 59.05	4872.05 138.00
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	2084.95 59.05	4799.75 135.95
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	2084.95 59.05	4721.25 133.70
iv)	Cement sand mortar 1 : 5	Cu.m. Cu.ft.	2084.95 59.05	4676.15 132.45
v)	Cement sand mortar 1 : 6	Cu.m. Cu.ft.	2084.95 59.05	4643.95 131.50
<b>c) 8" (200 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m. Cu.ft.	1304.90 36.95	4651.65 131.75
ii)	Cement sand mortar 1 : 3	Cu.m. Cu.ft.	1304.90 36.95	4567.55 129.35
iii)	Cement sand mortar 1 : 4	Cu.m. Cu.ft.	1304.90 36.95	4476.15 126.75



Sr. No.	Description	Unit	Rate (Rs.)	
			Labour	Composite
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4423.50
		Cu.ft.	36.95	125.30
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4385.95
		Cu.ft.	36.95	124.20
				
<b>d) 12" (300 mm) thick hollow block masonry</b>				
i)	Cement sand mortar 1 : 2	Cu.m.	1304.90	4345.30
		Cu.ft.	36.95	123.05
ii)	Cement sand mortar 1 : 3	Cu.m.	1304.90	4237.45
		Cu.ft.	36.95	120.00
iii)	Cement sand mortar 1 : 4	Cu.m.	1304.90	4120.30
		Cu.ft.	36.95	116.70
iv)	Cement sand mortar 1 : 5	Cu.m.	1304.90	4052.65
		Cu.ft.	36.95	114.75
v)	Cement sand mortar 1 : 6	Cu.m.	1304.90	4003.10
		Cu.ft.	36.95	113.35
10-5	Extra for hollow block masonry in first floor superstructure.	Cu.m.	454.45	454.45
		Cu.ft.	12.85	12.85
10-6	Extra for hollow block masonry in every additional floor above first floor.	Cu.m.	371.20	371.20
		Cu.ft.	10.50	10.50
10-7	Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m)	Cu.m.	83.55	98.15
		Cu.ft.	2.35	2.80