


| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-1 | Providing and laying 1:3:6 cement concrete block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (13mm) & down gauge including scaffolding, raking out joints and curing in basement. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2209.50 62.55 | 6357.10 180.05 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2209.50 62.55 | 6254.40 177.15 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2209.50 62.55 | 6194.00 175.40 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2209.50 62.55 | 6151.75 174.20 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1767.75 50.05 | 4944.65 140.05 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1767.75 50.05 | 4856.45 137.55 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1767.75 50.05 | 4804.55 136.05 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1767.75 50.05 | 4768.30 135.05 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1611.30 45.65 | 5436.40 153.95 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1611.30 45.65 | 5333.75 151.05 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1611.30 45.65 | 5273.35 149.35 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1611.30 45.65 | 5229.85 148.10 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| | i) Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 4732.00 134.00 |
| | ii) Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 4600.35 130.30 |
| | iii) Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1304.90 36.95 | 4523.05 128.10 |
| | iv) Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1304.90 36.95 | 4467.45 126.50 |



| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|---|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| 10-2 | Same as item 10-1 but in 1:2:4 concrete hollow block masonry. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2209.50 62.55 | 7025.75 198.95 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2209.50 62.55 | 6936.70 196.45 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2209.50 62.55 | 6834.00 193.55 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2209.50 62.55 | 6773.60 191.85 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2209.50 62.55 | 6731.35 190.65 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1767.75 50.05 | 5455.60 154.50 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1767.75 50.05 | 5379.05 152.35 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1767.75 50.05 | 5290.85 149.85 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1767.75 50.05 | 5238.90 148.35 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1767.75 50.05 | 5202.70 147.35 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1611.30 45.65 | 6052.90 171.40 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1611.30 45.65 | 5963.80 168.90 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1611.30 45.65 | 5861.15 166.00 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1611.30 45.65 | 5800.75 164.30 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1611.30 45.65 | 5758.45 163.10 |
| | d) 12" (300 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1304.90 36.95 | 5281.85 149.60 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 5167.60 146.35 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---------|--|--------|------------|-----------|
| | | | Labour | Composite |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1304.90 | 5034.75 |
| | | Cu.ft. | 36.95 | 142.60 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 4957.45 |
| | | Cu.ft. | 36.95 | 140.40 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 4901.85 |
| | | Cu.ft. | 36.95 | 138.80 |
| 10-3 | Providing and laying 1:3:6 cement concrete hollow block masonry using Lawrencepur sand and Margalla crushed aggregate 1/2" (12.7mm) thick and down gauge including scaffolding, raking out joints and curing in ground floor superstructure. | | | |
| | a) 4" (100 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2526.70 | 6646.25 |
| | | Cu.ft. | 71.55 | 188.25 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2526.70 | 6543.55 |
| | | Cu.ft. | 71.55 | 185.30 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2526.70 | 6484.35 |
| | | Cu.ft. | 71.55 | 183.65 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2526.70 | 6440.85 |
| | | Cu.ft. | 71.55 | 182.40 |
| | b) 6" (150 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 2084.95 | 5241.10 |
| | | Cu.ft. | 59.05 | 148.45 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 2084.95 | 5152.95 |
| | | Cu.ft. | 59.05 | 145.95 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 2084.95 | 5101.00 |
| | | Cu.ft. | 59.05 | 144.45 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 2084.95 | 5064.75 |
| | | Cu.ft. | 59.05 | 143.45 |
| | c) 8" (200 mm) thick hollow block masonry | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. | 1903.75 | 5704.45 |
| | | Cu.ft. | 53.90 | 161.55 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. | 1903.75 | 5601.75 |
| | | Cu.ft. | 53.90 | 158.65 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. | 1903.75 | 5542.60 |
| | | Cu.ft. | 53.90 | 156.95 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. | 1903.75 | 5500.30 |
| | | Cu.ft. | 53.90 | 155.75 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|-----------------|------------------|-------------------|
| | | | Labour | Composite |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 4708.85 133.35 |
| ii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 4577.15 129.65 |
| iii) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 1304.90 36.95 | 4501.10 127.45 |
| iv) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 1304.90 36.95 | 4445.50 125.90 |
| 10-4 | Same as item 10-3 but in 1:2:4 cement concrete hollow block masonry. | | | |
| a) 4" (100 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2526.70 71.55 | 7311.25 207.05 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2526.70 71.55 | 7223.40 204.55 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2526.70 71.55 | 7120.70 201.65 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2526.70 71.55 | 7060.30 199.95 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2526.70 71.55 | 7018.05 198.75 |
| b) 6" (150 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 2084.95 59.05 | 5749.60 162.85 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 2084.95 59.05 | 5673.05 160.65 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 2084.95 59.05 | 5584.90 158.15 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. Cu.ft. | 2084.95 59.05 | 5534.15 156.75 |
| v) | Cement sand mortar 1 : 6 | Cu.m. Cu.ft. | 2084.95 59.05 | 5497.90 155.70 |
| c) 8" (200 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. Cu.ft. | 1304.90 36.95 | 5713.60 161.80 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. Cu.ft. | 1304.90 36.95 | 5625.70 159.30 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. Cu.ft. | 1304.90 36.95 | 5523.05 156.40 |

| Sr. No. | Description | Unit | Rate (Rs.) | |
|---|--|--------|------------|-----------|
| | | | Labour | Composite |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 5462.65 |
| | | Cu.ft. | 36.95 | 154.70 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 5420.35 |
| | | Cu.ft. | 36.95 | 153.50 |
|  | | | | |
| d) 12" (300 mm) thick hollow block masonry | | | | |
| i) | Cement sand mortar 1 : 2 | Cu.m. | 1304.90 | 5256.20 |
| | | Cu.ft. | 36.95 | 148.85 |
| ii) | Cement sand mortar 1 : 3 | Cu.m. | 1304.90 | 5142.00 |
| | | Cu.ft. | 36.95 | 145.60 |
| iii) | Cement sand mortar 1 : 4 | Cu.m. | 1304.90 | 5010.35 |
| | | Cu.ft. | 36.95 | 141.90 |
| iv) | Cement sand mortar 1 : 5 | Cu.m. | 1304.90 | 4933.05 |
| | | Cu.ft. | 36.95 | 139.70 |
| v) | Cement sand mortar 1 : 6 | Cu.m. | 1304.90 | 4878.70 |
| | | Cu.ft. | 36.95 | 138.15 |
| 10-5 | Extra for hollow block masonry in first floor superstructure. | Cu.m. | 454.45 | 454.45 |
| | | Cu.ft. | 12.85 | 12.85 |
| 10-6 | Extra for hollow block masonry in every additional floor above first floor. | Cu.m. | 371.20 | 371.20 |
| | | Cu.ft. | 10.50 | 10.50 |
| 10-7 | Extra for cement concrete hollow block masonry of any description in any floor or other than building for every 5 ft (1.5m) height or part thereof beyond 15 ft (4.5m) | Cu.m. | 83.55 | 98.15 |
| | | Cu.ft. | 2.35 | 2.80 |